SCHEDULE - B

Name of the Work: Construction of Compound wall of Adjoining at Ward Office to Air Quarters Compound wall in Ward No. 18

Tender Notification: EE/H/TEND/12/13-14 date: 21/1/2014

Item No: 02

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms).	9.23	Cum	132.61	Rupees One Hundred Thirty Two And Paise Sixty One Only
2	Dismantling size stone masonry in clay mortar and stacking the size stone within a radius of 50m and removing the debris to a distance upto 200m.	9.18	Cum	291.40	Rupees Two Hundred Ninety One And Paise Forty Only
3	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work complete as per specifications. i) Ordinary soil - A. Manual Means (i) Depth upto 3 m. MORTH Specification No. 304	25.13	Cum	291.40	Rupees Two Hundred Ninety One And Paise Forty Only
4	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2	4.40	Cum	4122.94	Rupees Four Thousand One Hundred Twenty Two And Paise Ninety Four Only
5	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	11.04	Cum	3411.05	Rupees Three Thousand Four Hundred Eleven And Paise Five Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Sl No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
6	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not lesz than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13	3.41	Cum	4061.71	Rupees Four Thousand Sixty One And Paise Seventy One Only
7	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13(WITH AVAILABLE STONES)	5.51	Cum	2972.10	Rupees Two Thousand Nine Hundred Seventy Two And Paise Ten Only
8	KSRB 5.4-4 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4 , edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13	14.46	Cum	4559.82	Rupees Four Thousand Five Hundred Fifty Nine And Paise Eighty Two Only
9	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2	1.69	Cum	4592.00	Rupees Four Thousand Five Hundred Ninety Two Only
10	KSRB 15.1.3 Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	79.70	Sqm	76.80	Rupees Seventy Six And Paise Eighty Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
11	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications specification No. KBS 2.1(a) / 2.3.1	90.19	Cum	212.53	Rupees Two Hundred Twelve And Paise Fifty Three Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike